



1.5 Million Natural Gas Connections Project in 11 Governorates

Site-Specific Environmental and Social Impact Assessment



EGAS

Egyptian Natural Gas Holding Company

**Executive Summary
Sohag City /Sohag Governorate
September 2016**

Developed by



EcoConServ Environmental Solutions



**Petrosafe
Petroleum Safety & Environmental Services
Company**

EXECUTIVE SUMMARY

1 Introduction

The Government of Egypt (GoE) has immediate priorities to increase household use of natural gas (NG) by connecting 1.2 million households/yr to the gas distribution network to replace the highly subsidized, largely imported Liquefied Petroleum Gas (LPG).

The GoE is implementing an expansion program for Domestic Natural Gas connections to an additional 1.5 Million households over the next 4 years. The project presented in this study is part of a program that involves extending the network and accompanying infrastructure to connect 1.5 million Households in 11 Governorates between 2016 and 2019 with the assistance of a World Bank Loan of up to US\$500 Million and the Agence Française de Développement (French Agency for Development) financing of up to €70 Million. The program is estimated to cost US\$850 Million.

The ESIA objectives are as follow:

- Describing project components and activities of relevance to the environmental and social impacts assessments
- Identifying and addressing relevant national and international legal requirements and guidelines
- Describing baseline environmental and social conditions
- Presenting project alternatives and no project alternative
- Assessing potential site-specific environmental and social impacts of the project
- Developing environmental & social management and monitoring plans in compliance with the relevant environmental laws
- Documenting and addressing environmental and social concerns raised by stakeholders and the Public in consultation events and activities

As the project involves components in various areas within the 11 governorates, the consultation teams agreed with EGAS that site-specific ESIA's are to be prepared for each of the project sub-areas within the governorate. Guided by the 2013 Environmental and Social Impact Assessment (ESIAF) and Supplementary Environmental and Social Impact Assessment Framework (SSIAF), this is the site specific ESIA for the connections network and the expansion planned for the existing Pressure Reduction Station (PRS) in Sohag city. The project in Sohag City encompasses household connections and the expansion of an existing PRS in Sohag City from 10,000 m³/h to 20,000 m³/h PRS. The 5,000 households are to be connected in year 1 of the 3-yr project.

The local distribution company responsible for project implementation in Sohag city is Regions Gas Company (ReGas)

2 Project Description

2.1 Background

Natural Gas is processed and injected into the high pressure lines of the national Grid (70 Bar) for transmission. Upon branching from the main lines to regional distribution networks, the pressure of the NG is lowered to 7 Bar at the Pressure Reduction Stations (PRS). An odorant is



added to the NG at PRSs feeding distribution networks to residential areas¹ in order to facilitate detection. Regulators are then used to further lower the pressure to 100 mbar in the local networks, before finally lowering the pressure to 20 mbar for domestic use within the households. In addition to excavation and pipe laying, key activities of the construction phase also include installation of pipes on buildings, internal connections in households, and conversion of appliance nozzles to accommodate the switch from LPG to NG.

2.2 Project Work Packages

2.2.1 Off-take & Inlet connection/Pipeline “70 bar system”

In Sohag city there will be 15-m pipeline connection between off-take from the national high-pressure grid (70 bar) and PRS (Pressure Reduction Station).

2.2.2 Pressure Reduction Station (PRS)

PRS consists of equipment installed for automatically reducing and regulating the pressure in the downstream pipeline or main to which it is connected. Included are piping and auxiliary devices such as valves, control instruments, control lines, the enclosure, and ventilation equipment.

PRS for Sohag city has an inlet pressure range (70-18 bar) and outlet pressure 7 bar and maximum flow rate 10,000 SCM/H.

2.2.3 Main feeding line/network “7 bar system – PE 100”

A gas distribution piping system that operates at a pressure higher than the standard service pressure delivered to the customer. In such a system, a service regulator is required to control the pressure delivered to the customer.

Main feeding lines are mainly constructed from polyethylene pipes (HDPE) with maximum operating pressure (MOP) below 7 bar.

2.2.4 Distributions network “Regulators, PE80 Networks”

A gas distribution piping system in which the gas pressure in the mains and service lines is substantially the same as that delivered to the customer’s Meters. In such a system, a service regulator is not required on the individual service lines.

Distribution networks are mainly constructed from polyethylene pipes (MDPE) with MOP below 100 millibar.

2.2.5 Installations (Steel Pipes)

A gas distribution piping system consist of steel pipes which is connected from individual service line to vertical service pipe in a multistory dwelling which may have laterals connected at appropriate floor levels; in addition to service pipe connected to a riser and supplying gas to a meter and gas appliances on one floor of a building.

Internal Installation consists of a pipe connecting the pressure reducing regulator/district Governor and meter Outlet (MOP 25 millibar) to appliances inside the customer’s premises.

¹ Because natural gas is odorless, odorants facilitate leak detection for inhabitants of residential areas.



2.2.6 Conversions

Conversions involve increasing the diameter of the nozzle of the burner of an appliance to work with natural gas as a fuel gas rather LPG or others.

3 Legislative and Regulatory Framework

3.1 Applicable Environmental and Social Legislation in Egypt

- Law 217/1980 for Natural Gas
- Law 4 for Year 1994 for the environmental protection , amended by Law 9/2009 and law 105 for the year 2015.Executive Regulation(ER) No 338 for Year 1995 and the amended regulation No 1741 for Year 2005, amended with ministerial decree No 1095/2011, ministerial decree No 710/2012, ministerial decree No 964/2015, and ministerial decree No 26/2016
- Law 38/1967 for General Cleanliness
- Law 93/1962 for Wastewater
- Law 117/1983 for Protection of Antiquities
- Traffic planning and diversions
 - Traffic Law 66/1973, amended by Law 121/2008 traffic planning
 - Law 140/1956 on the utilization and blockage of public roads
 - Law 84/1968 concerning public roads
- Work environment and operational health and safety
 - Articles 43 – 45 of Law 4/1994, air quality, noise, heat stress, and worker protection
 - Law 12/2003 on Labor and Workforce Safety
 - Book V on Occupational Safety and Health (OSH)
 - Minister of Labor Decree 48/1967.
 - Minister of Labor Decree 55/1983.
 - Minister of Industry Decree 91/1985
 - Minister of Labor Decree 116/1991.

3.2 World Bank Safeguard Policies

Three policies are triggered for the project as a whole: Environmental Assessment (OP/BP 4.01), Physical Cultural Resources (OP/BP 4.11), and Involuntary Resettlement (OP/BP 4.12). However, OP/BP 4.12 will not be applicable to **Sohag city** as the expansion of the PRS will be within the existing Pressure Reduction Station premises. Additionally, the pipelines will pass through the main urban roads and side streets causing no damage to private assets or lands. In addition to the above mentioned safeguards policies, the Directive and Procedure on Access to Information² will be followed by the Project.

² <https://policies.worldbank.org/sites/ppf3/PPFDocuments/Forms/DispPage.aspx?docid=3694>



4 Analysis of Alternatives

4.1 No Project Alternative

This Natural Gas Connections to Households Project is expected to yield many economic and social benefits in terms of providing a more stable energy source, achieving savings in LPG consumption and enhancing safety in utilizing energy.

The No-Project alternative is not favored as it simply deprives the Egyptian Public and Government of the social, economic, and environmental advantages.

4.2 Energy Alternatives

- **Maintain LPG Use:** Introduction of piped natural gas to replace LPG will help to remove subsidies and reduce imports. The proposed project would also improve the safety of gas utilization as appliance standards are strictly controlled and only qualified personnel carry out installations and respond to emergencies. In the case of LPG, installations are not carried out by trained personnel resulting in possible unsafe installations and unsafe use of LPG.
- **Convert to Electricity:** The second alternative is to convert all homes to use electricity for all energy supply applications. Additional power stations would be needed to cope with the additional demand created by utilization of electricity in homes, which most probably would operate also by natural gas. Power losses in transmission and distribution are also significantly higher than their natural gas equivalents which would add to the overall inefficiency.
- **Use Renewables:** the renewables market does not present feasible, practical, and affordable alternatives to connecting 1.5 million households at this point in time in Egypt. Biogas requires large amounts of agricultural and domestic waste, while solar panels and heaters remain in pilot phase.

Energy alternatives do not provide favorable options to the proposed NG networking

4.3 Installation costs

The average natural gas connection installation cost is about 5600 EGP and consumers contribute a part of 1700 LE because the connection is heavily subsidized by the Government. This payment can be made either upfront or in installments over a period of time. Installment schemes are available to all community people.

The government of Egypt is negotiating with the project's financing organizations in order to secure additional subsidy to poor and marginalized groups. They also provide facilitation payments strategies through offering various installment schemes. The following are the main types of installments: 138 EGP/Month for 12 months, 74 EGP/Month for 24 months, 52 EGP/Month for 36 months, 42 EGP/Month for 48 months, 35 EGP/Month for 60 months, 31 EGP/Month for 72 months and 28 EGP/Month for 84 months

5 Environmental and Social Impacts and Mitigations

The environmental and social advantages of switching household fuel from LPG cylinders to natural gas pipelines are diverse. On the residential level, the proposed project will lead to



improved safety, reduced physical/social/financial hardships, and secure home fuel supply. On the national level, it promotes the utilization of Egyptian natural resources and reduces the subsidy and import burden.

A thorough analysis of environmental and social impacts is important to detail an effective management and monitoring plan which will minimize negative impacts and maximize positives.

The assessment of impacts distinguishes between the construction phase and the operation phase.



5.1 Positive Impacts

5.1.1 During the construction phase

Direct job opportunities to skilled and semi-skilled laborers

- The project is expected to result in the creation of job opportunities, both directly and indirectly. Based on similar projects implemented recently by EGAS and the local distribution company, the daily average number of workers during the peak time will be about 30 workers. The local community of Sohag Governorate could provide a proportion of this temporary labor force dependent on skills needed and the strategies of the individual contractors in sourcing their workforce.
- The total number of new short term job opportunities within the project areas is estimated at 20-30 temporary jobs.
- In order to maximize employment opportunities in the local communities it is anticipated that training will be required for currently unskilled workers. On-the-job training will also supplement opportunities for the local workforce for both temporary construction roles and also for long-term operation phase positions, where these are available.

Create indirect opportunities

- As part of the construction stage, a lot of indirect benefits are expected to be sensed in the targeted areas due to the need for more supporting services to the workers and contractors who will be working in the various locations. This could include, but will not be limited to accommodation, food supply, transport, trade, security, manufacturing... etc.

5.1.2 During the operation phase

- As indicated in the Baseline Chapter, women are key players in the current domestic activities related to handling LPG and managing its shortage. Being the party affected most from the shortfalls of the use of LPG, the NG project is expected to be of special and major benefits to women. This includes, but is not limited to, clean and continuous sources of fuel that is safe and does not require any physical effort and is very reasonable in the price of consumption fees. Time saving is among the benefits to women. The use of a reliable source of energy will allow women to accomplish the domestic activities in less time and this will potentially open a space for better utilization for the saved time.
- Constantly available and reliable fuel for home use
- Reduced expenditure on LPG importation and subsidies. As 5 thousand connections will be installed in Sohag Governorate. Each household consumes 1.3 LPG cylinders monthly. Accordingly, the total cylinders that will be reduced will be about 6500 thousand LPG per month. The subsidy value is about 70 EGP per each LPG cylinder. Consequently, the total saved monthly subsidy will be about 0.455 million EGP monthly. This will result in total annually savings of 5.46 million EGP. Additionally, significant savings will result due to replacing the electric water heater by NG heater
- Significantly lower leakage and fire risk compared to LPG
- Improved safety due to low pressure (20 mBar) compared to cylinders



- Beneficiaries to benefit from good customer service and emergency response by qualified personnel/technicians.
- Eliminate the hardships that special groups like the physically challenged, women, and the elderly had to face in handling LPG.
- Limiting possible child labor in LPG cylinder distribution

5.2 Anticipated Negative Impacts

5.2.1 Impact Assessment Methodology

To assess the impacts of the project activities on environmental and social receptors, a semi-quantitative approach based on the Leopold Impact Assessment Methodology the Buroz Relevant Integrated Criteria was adopted.

Detailed assessment matrices are shown in Annex 5 of in the SSESIA report of Sohag City. The table below presents the classification of impact ratings and respective importance of impact values.

Importance of Impact	Impact rating	
0-25	None or irrelevant (no impact);	
26-50	Minor severity (minimal impact; restricted to the work site and immediate surroundings)	
51-75	Medium severity (larger scale impacts: local or regional; appropriate mitigation measures readily available);	
76-300	Major severity (Severe/long-term local/regional/global impacts; for negative impacts mitigation significant).	

The following tables summarize the impacts and the corresponding mitigation measures within the management plan, in addition the monitoring plans proposed for implementation.



5.3 Environmental and Social Management Matrix during CONSTRUCTION

Table 1: Environmental and Social Management Matrix during CONSTRUCTION

Receptor	Impact	Mitigation measures	Roles and Responsibility			Estimated Cost of mitigation / supervision	
			Implementation	Direct supervision	Means of supervision		
Local traffic and accessibility	Traffic congestion (and associated noise/air emissions)	Excavation during off-peak periods	Excavation contractors	<ul style="list-style-type: none"> - LDC + - Traffic department 	Contractor has valid conditional permit + Field supervision	Contractor costs	
		Time limited excavation permits granted by local unit & traffic department					
		Announcements + Signage indicating location/duration of works prior to commencement of work	<ul style="list-style-type: none"> - LDC - Excavation contractors 	<ul style="list-style-type: none"> - LDC HSE - Local Unit - Traffic department 	Ensure inclusion in contract + Field supervision	LDC management costs	
		Apply Horizontal Directional Drilling under critical intersections whenever possible to avoid heavy traffic delays	Contractor	LDC HSE	Field supervision		
		Traffic detours and diversion	Traffic Department	Traffic Department	Traffic Department	Field supervision for detouring efficiency Complaints received from traffic department	Additional budget not required
		Road restructuring and closing of lanes				Fluidity of traffic flow	
Ambient air quality	Increased emissions of dust and gaseous pollutants	Controlled wetting and compaction of excavation/backfilling surrounding area	Excavation Contractor	LDC HSE	Contractual clauses + Field supervision	<ul style="list-style-type: none"> - Contractor costs - LDC management costs 	
		Isolation, covering, transportation and disposal of stockpiles			Contractual clauses + Field supervision		
		Compliance to legal limits of air emissions from all relevant equipment			Measure and document emissions of machinery by regular audits request emission measurements		



Receptor	Impact	Mitigation measures	Roles and Responsibility			Estimated Cost of mitigation / supervision
			Implementation	Direct supervision	Means of supervision	
<ul style="list-style-type: none"> - Ambient noise levels - Local community Workers 	<p>Increased noise levels beyond WB/National permissible levels</p>	<ul style="list-style-type: none"> - Ear muffs, ear plugs, certified noise PPE for workers 	<ul style="list-style-type: none"> - LDC Excavation Contractor 	LDC HSE	Contractual clauses + Field supervision (audits)	<ul style="list-style-type: none"> - Contractor costs - LDC management costs
		<ul style="list-style-type: none"> - Avoid noisy works at night whenever possible 			<ul style="list-style-type: none"> - Field supervision - Complaints receipt from local administration 	
<ul style="list-style-type: none"> - Underground utilities' integrity - Local community 	<p>Damage to underground utilities resulting in water/wastewater leaks, telecommunication and electricity interruptions</p>	<ul style="list-style-type: none"> - Coordination with departments of potable water, wastewater, electricity, and telecom authorities to obtain maps/ data on depth and alignment of underground utilities, whenever available 	Excavation Contractor	LDC HSE	<ul style="list-style-type: none"> - Official coordination proceedings signed by representatives of utility authorities - Examination of site-specific reports and records - Field supervision 	<ul style="list-style-type: none"> - Contractor management costs - LDC management costs
		<ul style="list-style-type: none"> - If maps/data are unavailable: Perform limited trial pits or boreholes to explore and identify underground utility lines using non-intrusive radio- cable and pipe locators 		LDC HSE Supervisor	<ul style="list-style-type: none"> - Contractual clauses + Field supervision 	
		<ul style="list-style-type: none"> - Preparation and analysis of accidental damage reports 		LDC HSE	<ul style="list-style-type: none"> - Review periodic HSE reports 	
		<ul style="list-style-type: none"> - Repair and rehabilitation of damaged components 		<ul style="list-style-type: none"> - LDC HSE - Local Government Unit - Local Police 	<ul style="list-style-type: none"> - Contractual clauses + Field supervision 	



Receptor	Impact	Mitigation measures	Roles and Responsibility			Estimated Cost of mitigation / supervision	
			Implementation	Direct supervision	Means of supervision		
<ul style="list-style-type: none"> - Streets (physical status) - local community and workers (health and safety) 	<p>Hazardous waste accumulation</p>	<ul style="list-style-type: none"> - Temporary storage in areas with impervious floor - Safe handling using PPE and safety precautions - Transfer to LDC depots for temporary storage - Disposal at licensed Alexandria hazardous waste facilities (Nasreya or UNICO) - Hand-over selected oils and lubricants and their containers to Petrotrade for recycling 	<ul style="list-style-type: none"> - LDC - Excavation Contractor 	LDC HSE	Field supervision and review of certified waste handling, transportation, and disposal chain of custody	<p>Indicative cost items included in contractor bid:</p> <ul style="list-style-type: none"> - Chemical analysis of hazardous waste - Trucks from licensed handler - Pre-treatment (if needed) - Disposal cost at Nasreya <p>Approximate cost of the above (to be revised upon project execution): 8,000-10,000 LE per ton</p>	
		<ul style="list-style-type: none"> - Adequate management of asbestos and any possible hazardous waste 	Water Authority + contractor			Field supervision + review of Water Authority manifests	<ul style="list-style-type: none"> - Contractor costs - LDC management costs
		<ul style="list-style-type: none"> - Minimize fueling, lubricating and any activity onsite that would entail production of hazardous materials empty containers 	<ul style="list-style-type: none"> - LDC - Excavation Contractor 			Field supervision	



Receptor	Impact	Mitigation measures	Roles and Responsibility			Estimated Cost of mitigation / supervision
			Implementation	Direct supervision	Means of supervision	
Local community	Non-hazardous waste accumulation	<ol style="list-style-type: none"> 1. Designate adequate areas on-site for temporary storage of backfill and non-hazardous waste 2. Segregate waste streams to the extent possible to facilitate re-use/recycling, if applicable 3. Reuse non-hazardous waste to the extent possible 4. Estimate size of fleet required to transport wastes. 5. <u>Transfer waste to Sohag disposal facility west of the city (near Beit Dawood and Beit Khallaf villages)</u> 	<ul style="list-style-type: none"> - LDC - Excavation Contractor 	LDC HSE	<ul style="list-style-type: none"> - Contractual clauses - Monitoring of waste management plan - Field supervision 	<ul style="list-style-type: none"> - Contractor costs - LDC management costs
Local community	Destruction of streets and pavement	<ul style="list-style-type: none"> - Arrange Restoration and re-pavement (رد الشئ لأصله) with local unit - Communication with local community on excavation and restoration schedules. 	<ul style="list-style-type: none"> - LDC in cooperation with the LGU 	EGAS	Field supervision Coordination with LGUs as needed	Included in re-pavement budget agreed by LDC with local units or Roads and Bridges Directorate
Occupational health and safety	Health and safety	<ol style="list-style-type: none"> 1. Full compliance to EGAS and LDC HSE requirements, manuals, and actions as per detailed manuals developed by Egypt Gas 2. Ensure the provision of the appropriate personal protective Equipment and other equipment needed to ensure compliance to HSE manuals 	Excavation Contractor	LDC HSE and EGAS SDO	Field supervision	<ul style="list-style-type: none"> - Contractor costs - LDC management costs



Receptor	Impact	Mitigation measures	Roles and Responsibility			Estimated Cost of mitigation / supervision
			Implementation	Direct supervision	Means of supervision	
Local communities and businesses	Lack of accessibility to businesses due to delay in street rehabilitation	<p>Compliance with the Environmental management plan concerning timely implementation of the construction schedule to minimize impact on local business</p> <ul style="list-style-type: none"> Follow up the procedure of Grievance Redress Mechanism Ensure transparent information sharing 	<p>During digging process</p> <p>LDC</p> <p>The sub-contractors</p>	LDC EGAS (SDO)	<ul style="list-style-type: none"> Ensure the implementation of GRM Supervision on Contractors performance 	No cost
Local community Health and safety	Threat to Safety of users and houses (due to limited level of awareness and misconceptions)	<p>Prepare Citizen engagement and stakeholder plan</p> <p>Awareness raising campaigns should be tailored in cooperation with the community-based organizations</p>	<p>During the construction</p> <p>LDC</p>	LDC EGAS (SDO)	<ul style="list-style-type: none"> List of awareness activities applied Lists of participants Documentation with photos Awareness reports 	<ul style="list-style-type: none"> 2250 \$ per awareness raising campaign 2250 \$ for brochure and leaflets to be distributed (material available by EGAS-\$ spent)



5.4 Environmental and Social Monitoring Matrix during CONSTRUCTION

Table 2: Environmental and Social Monitoring Matrix during CONSTRUCTION

Receptor	Impact	Monitoring indicators	Responsibility of monitoring	Frequency of monitoring	Location of monitoring	Methods of monitoring	Estimated Cost of monitoring
Local traffic and accessibility	Reduction of traffic flow and accessibility to local community	Comments and notifications from Traffic Department	LDC HSE	Monthly during construction.	Construction site	Documentation in HSE monthly reports Complaints log	LDC management costs
Ambient air quality	Increased air emissions	HC, CO% and opacity	LDC HSE	Once before construction + once every six months for each vehicle	Vehicles licensing Department	Measurements and reporting of exhaust emissions of construction activities machinery Complaints log	LDC management costs
Ambient noise levels	Increased noise levels	Noise intensity, exposure durations and noise impacts	LDC HSE	Regularly during site inspections and once during the night in every residential area or near sensitive receptors such as hospitals	Construction site	Measurements of noise levels Complaints log	LDC management costs
		Complaints from residents	LDC HSE	Monthly during construction.	Construction site	Documentation in HSE monthly reports	LDC management costs
Underground utilities	Damages to underground utilities and infrastructure	Official coordination reports with relevant authorities Accidents documentation	LDC HSE	Monthly during construction.	Construction site	Documentation in HSE monthly reports	LDC management costs
Physical state of street	Waste generation	Observation of accumulated waste piles	LDC HSE	During construction. Monthly reports	Construction site	Observation and documentation	LDC management costs



Receptor	Impact	Monitoring indicators	Responsibility of monitoring	Frequency of monitoring	Location of monitoring	Methods of monitoring	Estimated Cost of monitoring
		Observation of water accumulations resulting from dewatering (if encountered)	LDC HSE	During construction. Monthly reports	Around construction site	Observation and documentation	LDC management costs
		Chain-of-custody and implementation of waste management plans	LDC HSE	Zonal reports	Construction site and document examination	Site inspection and document inspection	LDC management costs
Local community	Damaging to the streets	<ul style="list-style-type: none"> – Streets quality after finishing digging – Number of complaints due to street damage 	LDC, EGAS	Four times per year, each three months	Site and Desk work	Checklists and complaints log	No cost
Local community	Threat to Safety of users and houses (due to limited level of awareness and misconceptions)	<ul style="list-style-type: none"> – Number of awareness raising implemented – Number of participants in information dissemination 	LDC, EGAS	Quarterly monitoring	Office	Reports Photos Lists of participants	No cost



5.5 Environmental and Social Management Matrix during OPERATION

Table 3: Environmental and Social Management Matrix during OPERATION

Receptor	Impact	Mitigation measures	Responsibility of mitigation	Responsibility of direct supervision	Means of supervision	Estimated Cost of mitigation / supervision
<ul style="list-style-type: none"> - Ambient air quality - Community health and safety 	Network integrity	<ul style="list-style-type: none"> - Detailed review of the geotechnical and geological history of the project area - Development of a full emergency response plan in case of rare events which exhibit multiple simultaneous impacts - Random inspections and awareness campaigns to ensure that NG piping and components (both inside the household and outside) are not be altered, violated, or intruded upon in any way without written approval from, or implementation of the alteration by, the LDC. 	LDC	LDC HSE.	<ul style="list-style-type: none"> - Map and local geotechnical report review - Site inspections - Awareness actions - Periodical trainings and drills 	LDC management costs
<ul style="list-style-type: none"> - Ambient air quality - Community health and safety 	Repairs and maintenance (network and households)	As with construction phase activities	<ul style="list-style-type: none"> - LDC - Excavation Contractor 	LDC HSE	As relevant from construction phase	LDC management costs



Receptor	Impact	Mitigation measures	Responsibility of mitigation	Responsibility of direct supervision	Means of supervision	Estimated Cost of mitigation / supervision
<ul style="list-style-type: none"> - Ambient air quality - Occupational health and safety - Community health and safety 	<p>Management of odorant and its containers</p>	<ul style="list-style-type: none"> - Strict use of chemical-resistant suits and PPE when handling odorant barrels, tanks, or spills - Evacuation of odorant from barrels into holding tank with utmost care and full PPE - Covering possible odorant spills immediately with sand and treatment with sodium hypochlorite as per EGAS and LDC practices - On-site treatment of empty containers with sodium hypochlorite and detergent as Per EGAS and LDC practice - Ship empty containers to a certified hazardous waste facility via company depot using certified handling and transportation contractors - Ensure full and empty (treated) odorant containers are accompanied by a trained HSE specialist during transportation to and from the depot and to/from the hazardous waste disposal facility (UNICO and/or Nasreya) - Others measures as per QRA 	<p>PRS staff</p>	<p>LDC HSE</p>	<p>Quarterly auditing for each PRS</p>	<p>Cost to be included in PRS running budget:</p>
<ul style="list-style-type: none"> - Ambient noise - Occupational health and safety - Community health and safety 	<p>Noise of PRS operation</p>	<ul style="list-style-type: none"> - Locate noisy pressure reducers away from PRS borders in residential areas - Others measures as per QRA 	<p>LDC Design Department</p>	<p>LDC HSE</p>	<p>Review of PRS layout</p>	<p>LDC management costs</p>
		<ul style="list-style-type: none"> - Build barrier walls between reducers and sensitive receptors when needed 	<p>Contractor</p>	<p>LDC HSE</p>	<p>Field supervision of PRS construction</p>	<p>Contractor costs</p>



Receptor	Impact	Mitigation measures	Responsibility of mitigation	Responsibility of direct supervision	Means of supervision	Estimated Cost of mitigation / supervision
<ul style="list-style-type: none"> - Ambient air quality - Occupational health and safety - Community health and safety 	Leakage and fire	<ul style="list-style-type: none"> - Mitigations based on Quantitative Risk Assessments 	Independent consultant	LDC HSE	QRA Document review	LDC management costs & PRS cost
<ul style="list-style-type: none"> - Ambient air quality - Occupational health and safety - Community health and safety 	Potential risks due to PRS Operation	<ul style="list-style-type: none"> - Remote actuation of isolation and slam-shut valves by LDC for PRS and pipelines. 	Designer	LDC Project Dept.	PRS design Document Review	Additional budget not required
		<ul style="list-style-type: none"> - Produce Hazardous Area Classification drawings - Control room exit design 	Designer	Eng. / Elect. Dept. Projects Dept.	Drawing and design Document Review	Additional budget not required
		<ul style="list-style-type: none"> - Preventive maintenance policy and station manual 	contractor + LDC	Engineering Dept.	Policy and manual review	Included in PRS cost
		<ul style="list-style-type: none"> - Provision of self-contained breathing apparatus (2 pieces for each station) for handling odorant leaks 	LDC	HSE Dept.	Inspection by operators	Included in PRS cost
		<ul style="list-style-type: none"> - Apply jet fire rated passive fire protection system to all critical safety shutdown valves ESDVs or Solenoid valves (As applicable) 	Designer	LDC Projects Dept.	Component inspection and design document review	Included in PRS cost



Receptor	Impact	Mitigation measures	Responsibility of mitigation	Responsibility of direct supervision	Means of supervision	Estimated Cost of mitigation / supervision
		- Place signs in Arabic and English "Do Not Dig" and "High Pressure Pipeline Underneath"	LDC	Engineering Dept.	Signage inspection and site visits	Additional budget not required
		- Install an elevated wind sock and provision of portable gas detectors	LDC	HSE Dept.	Design and implementation review	Included in PRS cost
		- The design should fully comply with IGE TD/3 code requirements	Designer	Project Dept.	Design document review	LDC management costs
		- Any other measures as per QRA	LDC	EGAS	As per QRA	As per QRA
Economically disadvantaged Community members	Financial burden on economically disadvantaged due to the installments	- Petro Trade should collect the installment immediately after the installation of NG - The installments should be collected on monthly basis in order not to add burden to the poor, as it will be easier for them to pay on monthly basis - The installment should not be high	Petro trade (Company responsible for collecting the consumption fees and the installments)	EGAS	Banks loans log Complaints raised by poor people due to the frequency of collecting the installments	No cost
Informal LPG distributors	Loss of revenue for LPG distributors	- LPG distributors should be informed about the NG potential areas in order to enable them to find alternative areas - They should be informed about the GRM in order to enable them to voice any hardship	Butagasco	EGAS	Information sharing activities with the LPG vendors Grievances received from them	No cost
Community health and safety	Possibility of Gas leakage	- Information should be provided to people in order to be fully aware about safety procedures - The hotline should be operating appropriately - People should be informed of the Emergency Numbers	LDC	LDC	Complaints raised due to Gas leakage	No cost



5.6 Environmental and Social Monitoring Matrix during OPERATION

Table 4: Environmental and Social Monitoring Matrix during OPERATION

Impact	Monitoring indicators	Responsibility of monitoring	Monitoring Frequency	Location of monitoring	Methods of monitoring	Monitoring Estimated Cost
Network integrity	<ul style="list-style-type: none"> - Earthquakes or geotechnical settlements - Emergency response time and corrective actions during emergency drills - Reports of alteration or tampering with ANY gas components 	LDC HSE	Bi-annual inspections and annual emergency response drills	Along the network and inside and outside households	- Inspection, leakage detection, running the drills	LDC management costs
Improper management of odorant during operation	<ul style="list-style-type: none"> - Log of spillage incidents - Number of treated containers - Odorant delivery forms 	LDC HSE	Quarterly for each PRS	PRSs	- Compare Environmental Register with odorant delivery forms, observation of site	LDC management costs
Noise of PRS operation	<ul style="list-style-type: none"> - Noise intensity 	LDC HSE	Quarterly for each PRS	PRSs	- Noise meter	LDC management costs
Financial burden on economically disadvantaged due to the installments	<ul style="list-style-type: none"> - Number of economically disadvantaged people who complained - Number of those who can't pay the installment 	LDC and Petro Trade, EGAS	Quarterly	Desk work	<ul style="list-style-type: none"> - Complaints log - Bank reports - Petro trade reports 	No cost
Impact on the informal LPG distributors	<ul style="list-style-type: none"> - Grievance received from the informal LPG distributors - Information shared with them 	EGAS, LDC	Quarterly	Desk work	- Complaints log	No cost
Possibility of Gas leakage	<ul style="list-style-type: none"> - Complaints raised by the community people - Number of leakage accidents reported/raised 	LDC, EGAS	Four times per year, each three months	Site and Desk work	Complaints log LDC	No cost



6 Stakeholder Engagement and Public Consultation

The public consultation chapter aims to highlight the key consultation and community engagement activities that took place as part of the preparation of the ESIA and their outcomes. Following are the main groups consulted during the SSESIA and the engagement tool used.

Table 5: Summary of Consultation Activities in Sohag Governorate

participants	Number		Methods	Date
	Male	Female		
During the site specific study				
Government officials	22	4	In-depth	September and October 2015
Governmental and NGOs	5	1	In-depth	
Community people	33	46	FGD	
Community people	314	215	Structured questionnaire	
Potential beneficiaries, government officials, NGO representatives,	89	33	Public consultation	14 th of February 2016
Total	463	299		

6.1 Main Results of Consultation Activities

The majority of sample surveyed expressed very high demand on the project. They also indicated their willingness to be connected to the NG regardless to the amount of money they can afford to pay. 56.1% of them were willing to pay the installation cost in cash. This high level of enthusiasm from the local communities towards the project is attributed to the high level of awareness of the benefits of the natural gas and the current hardships that the households are facing to secure LPG.

Table 6: Sample of the key comments and concerns raised during the consultation activities

Subject	Questions and comments	Responses
Sanitation problem in Sohag and the reasons to have sanitation installed prior to the NG	Almost all participants were keen to share their problems associated with the sanitation coverage. Their opinion is that absence of sanitation infrastructure should not prohibit the installation of NG in the Area	Presence of Sewage/sanitation infrastructure prior to installing NG infrastructure is crucial. For safety reasons, NG should be the final ground utility installed in any area. There are currently several projects to increase coverage of sanitation infrastructure in Sohag
Timing of NG Installation	When will the NG installed to the houses?	A specific plan was prepared to install the NG to various areas
Lack of “one-stop shop” to apply for the NG connection	NG customers don’t have one place to go to for applying to install the NG.	The customers can go to a contracting office to have the NG installed to their house. However, the customer must provide electricity bill and lease/ ownership contract of their household.



Subject	Questions and comments	Responses
Problems associated with NG connection and grievance mechanism	Many complaints were presented to the Gas company without being solved. To whom should we address our complaints?	The aggrieved person can present his complaint to customer service within Regas
Temporary closed apartments problem	In case of having a closed apartment during the project, will it be able to connect to the NG later on?	During construction phase, the apartment can be connected to the NG for 1700 EGP. After the construction phase the closed apartments can be connected but they will have to pay the full unsubsidized cost of installation
People reluctance to connect to sanitation system	The community people in some areas are not keen to be connected to sanitation network. That will deprive them from the NG.	According to the technical requirements. The NG should be last ground utility
New areas that will benefit of sanitary system	El Maragha District will benefit from the world bank sanitation connection. Will they be part of the NG installation plan?	The Plan is dynamic , it might be enhanced and changed according to the availability of sanitation network
Role of the NGOs	What is the role of the NGOs?	They will play a major role in information sharing process and mobilizing the community to have the NG installed
How the installation plan was developed?	What are the standards and requirements the connection plans were based on? How did the plans manage to define the number of beneficiaries?	Regas have already conducted a P&A survey that enabled them to put estimations about the number of beneficiaries who are technically accepted
Lack of sufficient space in the street to install the NG in	In Akhmim, the streets are too narrow and it will be difficult to install the NG pipelines there, how such problem can be solved	The exact venue should be identified on the map and solutions can be proposed if possible
Illegal constructions	Some illegal construction were built in Sohag. They closed the entrance of streets how such problem can be solved?	It falls under the responsibility of the local governmental units. Such constructions are dealt with according to the law

6.2 Summary of Consultation Outcomes

The consulted groups expressed their eagerness and interest to have the NG installed to their areas. Aside from the overwhelming interest in the project, some concerns were reported by the consulted groups. The main concern raised was about technical specifications required to install the NG to participants' residential units. Aside from the lack of sanitation, the consulted groups were interested to get information about the NG installation time plan. There was a concern pertaining to contracting problems. Various stakeholders were also keen to obtain information about grievance mechanism.



Site specific consultation efforts included all concerned stakeholders (e.g. individuals/ households affected by the project activities, civil society organizations representing the interest of the community, or regulatory and governmental bodies who will play a role in facilitating or regulating the implementation of site-specific project activities.

While WB safeguards and regulations state that a minimum of two large-scale, well-publicized public consultation sessions are a must for projects classified as category ‘A’ projects like the one at hand³, additional consultation activities (for example through focus group discussions, in-depth meetings, and interviews) were implemented to reach the most vulnerable and hard to reach community members. Additionally, in order to obtain larger scale and more quantifiable information, the consultant conducted surveys in the different project sites.

³ Clause 14 of OP 4.01 states that: “For Category A projects, the borrower consults these groups at least twice: (a) shortly after environmental screening and before the terms of reference for the EA are finalized; and (b) once a draft EA report is prepared. In addition, the borrower consults with such groups throughout project implementation as necessary to address EA-related issues that affect them.”

